

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the approximate estimate quantities of work to be done for constructing a dispensary building and maternity ward at Devarayasamudram.

Serial No.	Items of work	Per	Dispensary	Maternity ward	Kitchen for Maternity ward	Kitchen for Dispensary	Latrine
1	Earthwork excavation and filling in basement ..	C. yd.	50	47	4		4
2	Concrete in mortar ..	C. ft.	304	421	..		..
3	Burnt stone in chunam ..	..	1,311	1,097	173		116
4	Burnt brick in chunam ..	..	1,722	1,690	195		166
5	Plastering with chunam ..	Sqr.	30.59	29.56	5.29		4.18
6	White and colour washing ..	..	30.59	29.56	5.29		..
7	Teak wood work wrought and put up ..	C. ft.	83.81	48.00	11.42		..
8	Roofing with 1st class Mangalore tiles on teak rafters, etc., complete.	Sqr.	12.91	10.66	1.92		..
9	Ridge tiles set in mortar with cement pointing ..	R. ft.	31	31	15		..
10	Flooring with Chudapah slabs on 3" concrete bed and cement pointing.	Sqr.	1.66	2.83	.70		..
11	Flooring with Mangalore square tiles over 3" concrete bed and cement pointing.	..	4.80	2.40	..		..
12	Burnt stone slabs 6" thick dressed ..	S. ft.	167	269	15		..
13	Teakwood battened doors with double shutters with iron clamps, etc., complete.	..	112	142	18		..
14	Teakwood windows with panelled and glazed shutters with 3/4" iron bars clamps, etc., complete.	..	118	..	5		..
15	Teakwood ventilators with glazed shutters, etc., complete.	..	9	12	..		..
16	Silicate painting or chacolate ..	Sqr.	5.80	4.03	.46		..
17	Teakwood pillars with base and capitals dressing	Each	4	..	..		..
18	Chunnam borders ..	R. ft.	80	..	27		..
19	Providing almirah in compounding room 3 1/2' x 4 1/2' with teak planks 1" thick.	Each	2	..	..		..
20	Providing wooden racks in the store room ..	Lump sum	..	..	..		..
21	Chunnam pointing ..	Sqr.	2.47	2.24	..		Lump sum
22	Clearing site and leveling ground ..	Lump sum	..	..	..		Lump sum
23	Wood oiling ..	Do	..	..	..		..
24	Tarring ..	Do	..	..	..		..
25	Ventilating tile ..	Each	..	..	4		Lump sum
26	Conducting V shaped drain ..	Lump sum	..	..	..		..
27	Providing drainage arrangements around the building.	..	..	..	..		384
28	Coping over wall with plastering ..	R. ft.	..	..	..		..
29	Teakwood battened shutters with frames for shelves.	S. ft.	..	56	..		..
30	Teakwood plank 1" thick for shelves ..	..	..	34	..		..
31	Providing teakwood racks, and cistern wall in bath room.	Lump sum	..	..	..		..
32	Teakwood pillars with base and caps complete 3" x 5" square	No.	..	5	..		..
33	Teakwood battened windows with iron bars, including glazed shutters, etc., complete.	S. ft.	..	36	..		..

R. L. STEELE,

Executive Engineer,

SPECIAL WATER-SUPPLY CONSTRUCTION DIVISION.

Abstract Notification, dated 19th December 1924.

The attention of the public is hereby invited to the detailed notice calling for sealed tenders for the construction of the Filter beds, Service Reservoir, Settling tanks, Watchmen shed and Temporary office shed for water-supply to Tumkur Town" published in pages 5 to 8 of Part VI of the *Mysore Gazette*, dated 1st January 1925. The last date for receiving the tenders is 12 noon of 3rd February 1925.

H. F. MARKER,

Executive Engineer.

Special Water-Supply Construction Division